

# Finished Construction & Noggin Requirements

All Sectional Doors and Flex-a-Doors

- Day Light Opening (DLO):** Height & width of finished opening with all jambs on, and a finished, level floor.
- Finished **Head Room Clearance (HRC):** Panelift doors: standard 340 mm, restricted 300 mm, (less- ask rep).
- Finished **Side Room Clearance (SRC):** Minimum 150mm clearance required both sides of opening
- Finished **Solid Side Room Fixing (SSF):** Minimum solid fixing required both sides of opening (CSI120 PFT120 PFI140 AS125 FX120)
- Internal face of opening must be completed on one flush plane.
- Solid noggin fixings points required as framing timber, concrete, block, or up to 6mm steel.
- Noggins must be set flush beneath linings, metal ceiling battens must not intrude through noggins.
- Square-set is preferred over cornice (as they may have to be cut).

Panel Doors Opening height up to	Track Noggins			Motor Noggins			
	Set 1	Set 2	Set 3	Steel	Ext	Alum	Ext
2430	2200			3200			
over 5200 wide or insulated	1100	2200					
3200	1300	2600		4000	1	4300	1
3500	1300	2400	3500	4800	2	4300	1
4000					2	5300	2

B&D Flex-a-door Opening height up to	Track Noggins			Motor Noggins			
		Set 2	Set 1	Steel	Ext	Alum	Ext
2130		1800		3200			
2790		1800	2400	4000	1	4300	1

